

Inspecting for Water Pollution Control on Construction Sites



Who Are We?

➡ Part of Caltrans' Overall Water Quality Program

- ➡ Testing, Sampling, Monitoring, GIS, BMP Design, Pilot Studies for Construction, Maintenance, Operations of Highways

➡ Storm Water Task Force

- ➡ 5,000+ Compliance Inspections ...All Caltrans Districts
- ➡ 2000+ Trained
- ➡ 400+ SWPPPs Prepared/Reviewed
- ➡ Specifications/Manuals Prepared

➡ Your Facilitator

➡ Audience Introductions



Why Are You Here?

- ➔ **To Learn About Past and Current Regulatory Issues**
- ➔ **To Comply With Permit Requirements for Training.**
- ➔ **To Review Caltrans' General Requirements for Water Pollution Control on Construction Sites**
- ➔ **To Be Introduced to the New Specifications and Manuals**



What You Will Learn

- ➔ **Why Water Pollution Should be Prevented**
- ➔ **Monetary Fines are Real**
- ➔ **Which Documents Govern on Caltrans Construction Sites**
- ➔ **Correct and Incorrect BMP Installations**
- ➔ **How to Prepare for and Conduct WPC Inspections**
- ➔ **What to Expect and Do During Regulatory Inspections**
- ➔ **How to Handle the Paperwork**



Glossary

- ➡ **NPDES** - National Pollutant Discharge Elimination System
- ➡ **SWMP** - Storm Water Management Plan
- ➡ **SWPPP** - Storm Water Pollution Prevention Plan
- ➡ **WPCP** - Water Pollution Control Program
- ➡ **BMP** - Best Management Practice
- ➡ **EPA** - Environmental Protection Agency
- ➡ **SWRCB** - State Water Resources Control Board
- ➡ **RWQCB** - Regional Water Quality Control Board
- ➡ **NRDC** - Natural Resources Defense Council
- ➡ **CSWC** – Construction Storm Water Coordinator
- ➡ **SWTF** - Storm Water Task Force

Introduction

➡ Course Highlights


- ⇒ Introduction
- ⇒ The Law
- ⇒ Recent Fines
- ⇒ Permits, Specs and Manuals
- ⇒ Construction Site BMPs
- ⇒ Inspection Procedures
- ⇒ Communication
- ⇒ Documentation



Introduction

Construction Site Pollutants

Erosion and Sedimentation



Construction Wastes



Introduction

- ➡ One gallon of oil has the potential to contaminate up to one million gallons of water

StormWater/CleanWater protection program



Introduction

- ➔ Forty percent of all U.S. waters are not fishable or swimmable, according to the U.S. EPA
- ➔ “Even a partial accounting shows that hundreds of millions of dollars are lost each year....due to urban stormwater pollution”


Natural Resources Defense Council



Introduction

Water Pollution Prevention

- ➡ Overall Purpose
 - ⇒ To Reduce Potential Environmental and Human Health Impacts
 - ⇒ Comply with State and Federal Laws



Introduction

- ➔ Sediment, the most common pollutant washed from construction sites, clogs the gills of fish, blocks light transmission and increases ocean water temperature
.....harming aquatic life, and disturbing the food chain



Introduction

- ➡ Construction site erosion can be 10 to 1,000 times greater than nature's erosion process


Ohio Department of Transportation



Introduction

Construction Site Water Pollution Prevention

- ➡ Minimize the Potential Impact that Construction Activities may have on Water Bodies and Protect their Beneficial Uses for Future Generations



The Law

➡ Course Highlights

- ⇒ Introduction
- ⇒ The Law
- ⇒ Recent Fines
- ⇒ Permits, Specs and Manuals
- ⇒ Construction Site BMPs
- ⇒ Inspection Procedures
- ⇒ Communication
- ⇒ Documentation



The Law

- ➔ 1972 Federal Clean Water Act (CWA)
 - ➔ Amend to Prohibit Any Discharge of Pollutants from a Point Source
- ➔ 1987 Amendments to the CWA
 - ➔ Added Section 402(p) Establishing the Framework for Regulations Regarding Municipal and Industrial Discharges
- ➔ 1990 EPA Published Final Regulations
 - ➔ Established Permit Requirements for Storm Water Discharges Associated with Industrial (Including Construction) Activities
- ➔ 1992 California's General Permit was Adopted
 - ➔ Established Requirements for Discharges Associated with Construction Activities
- ➔ 1999 Caltrans NPDES Permit was issued – 03 Permit
- ➔ California's Porter Cologne Water Quality Control Act



Who Enforces These Laws?

- ⇒ EPA
- ⇒ SWRCB / RWQCB
- ⇒ Other Agencies

- ⇒ **Private Citizens**
 - ⇒ NRDC
 - ⇒ Baykeepers
 - ⇒ Other Watchdog
 - ⇒ Groups



Recent Fines

➡ Course Highlights

- ⇒ Introduction
- ⇒ The Law
- ⇒ **Recent Fines**
- ⇒ Permits, Specs and Manuals
- ⇒ Construction Site BMPs
- ⇒ Inspection Procedures
- ⇒ Communication
- ⇒ Documentation



What If We Don't Comply?

- ➡ Fines to \$27,500 Per Day – Per CWA
- ➡ Fines to \$15,000 Per Day and \$20 a gallon – Per Porter Cologne Act
- ➡ Current Regulatory Atmosphere
 - ⇒ “The Learning Curve is Over”



Violation and Order for Compliance 1998 District 12

USEPA Region 9 Cited
Contractor and Agency
as Follows:

➡ “...excessive amounts
of sediment to the
storm drain...”



\$11,000

Violation and Order for Compliance 1998 District 7

- ⇒ “...excessive amounts of sediment to the storm drain...”
- ⇒ “...discharge of false work and miscellaneous construction debris to ...Creek and ... River.”
- ⇒ “ A sheen of fuel floating on the storm water ... 40 feet from a drain inlet.”



Violation and Order for Compliance 2000 County of Sacramento

- ➡ Lower Laguna Bypass Roadway Construction
 - ⇒ “Violated permit for discharges of sediment”
 - ⇒ “Failed to Develop a SWPPP”
- ➡ County waived the appeal and paid the penalty



\$52,400

Violation and Order for Compliance 2000 Home Builder...Redding

⇒ “No effective erosion control and minimal sediment control measures....”

⇒ Notes:

- ⇒ EPA visited the site in 1998 and 1999
- ⇒ RWQCB issued two prior violation notices that went unheeded



Violation and Order for Compliance 1998 District 11

➡ “..sloppy runoff-control practices at Caltrans construction sites, drainage facilities and maintenance yards”

San Diego Baykeeper




\$430,000

Violation and Order for Compliance 2000

City of San Diego

➡ “Failing to curb erosion along a dirt road above the Los Penasquitos Lagoon”

\$527,000



Permits, Specifications, and Manuals

➡ Course Highlights

- ⇒ Introduction
- ⇒ The Law
- ⇒ Recent Fines
- ⇒ **Permits, Specs and Manuals**
- ⇒ Construction Site BMPs
- ⇒ Inspection Procedures
- ⇒ Communication
- ⇒ Documentation



Permits

- ➡ General Construction Permit CAS000002 - The '02 permit
 - ➡ Caltrans NPDES Permit CAS000003 - The '03 permit
-
- ⇒ The 02 Permit was amended in 2001 to include monitoring
 - ⇒ The 03 Permit requires that Caltrans' construction program complies with the General Construction Activity Permit for construction sites that disturb 5 acres or more
 - ⇒ Both permits can be viewed and downloaded from the State Water Resources Control Board website, www.swrcb.ca.gov

Specifications


➡ Caltrans Standard Specifications, Section 7-1.01G

- ⇒ Requires contractors to prepare and implement a program to control water pollution effectively during the construction of all projects.
- ⇒ SWPPP/WPCP and BMPs must meet requirements of this section
- ⇒ Key Points
 - 70,000 m² (17 acres) rule
 - Scheduling

➡ Sections 10,16,18, and 20


Contract Special Provisions

- ⇒ **Contract Special Provisions - Section 10**
 - ⇒ Issued to satisfy the NPDES Permit requirements
 - ⇒ Defines water pollution control requirements



Contract Special Provisions


- ➡ **Contents of Water Pollution Control Section**
 - ➡ Identifies plan required (SWPPP or WPCP)
 - ➡ Statewide or Local Permit, Other Agency Permits
 - ➡ Identifies Caltrans Storm Water Quality Handbooks – 1997 or 2000



Contract Special Provisions

➡ Contents of Water Pollution Control Section (Cont.)


- ➡ The SWPPP/WPCP contents and approval process
- ➡ Additional required BMPs
- ➡ Identifies cost breakdown requirements
- ➡ Identifies Permanent Control Measures
- ➡ Designation of a WPC Manager (New)



Contract Special Provisions

➡ Contents of Water Pollution Control Section (Cont.)


- ➡ Defines active and non-active Disturbed Soil Areas (DSAs)
- ➡ Defines the rainy and non-rainy seasons
- ➡ Defines maximum active DSAs during the rainy season – usually 5 acres
- ➡ Rainy season implementation plan (New)



Contract Special Provisions

➡ Contents of Water Pollution Control Section (Cont.)

- ➡ Inspection and maintenance requirements
- ➡ Move-In/Out (Permanent Erosion Control - New)
- ➡ Maintenance cost sharing on some BMPs (New)
- ➡ Progress Payments / Retention
- ➡ Runoff Monitoring (New)



Manuals


➡ Caltrans Storm Water Quality Handbooks

- ➡ Project Planning and Design Guide
- ➡ SWPPP / WPCP Preparation Manual
- ➡ Construction Site BMPs Manual
 - 1997 Contractors Guide

Get Manuals online at

<http://www.dot.ca.gov/hq/construc/stormwater.html>

or hard copies are available from Caltrans Publications



➡ Revised Construction Manual

➡ New BMP Field Guidance Manual

➡ New Dewatering Guide

Manuals


➡ Caltrans Storm Water Quality Handbooks

- ➡ Project Planning and Design Guide
- ➡ SWPPP / WPCP Preparation Manual
- ➡ Construction Site BMPs Manual

➡ Revised Construction Manual

➡ New BMP Field Guidance Manual

➡ New Dewatering Guide



Manuals


➡ Caltrans Storm Water Quality Handbooks

- ⇒ Project Planning and Design Guide
- ⇒ SWPPP / WPCP Preparation Manual
- ⇒ Construction Site BMPs Manual

➡ Revised Construction Manual

➡ New BMP Field Guidance Manual

➡ New Dewatering Guide



Manuals


➡ Caltrans Storm Water Quality Handbooks

- ⇒ Project Planning and Design Guide
- ⇒ SWPPP / WPCP Preparation Manual
- ⇒ Construction Site BMPs Manual

➡ Revised Construction Manual

➡ New BMP Field Guidance Manual


➡ New Dewatering Guide



Manuals

➡ Construction Site BMPs Manual

- ⇒ Guidelines for the selection and implementation of construction site BMPs
- ⇒ Major changes compared to 1997 Handbooks
 - Area requirements/Tables
 - Fiber rolls
 - Stockpile management
 - Entrances / exits
 - Dewatering




Manuals

➡ Construction Site BMPs Manual

⇒ Major changes compared to 1997 Handbooks (cont)

- New BMPs
- New # system
- Dropped BMPs
- Revisions to soil stabilizers
- Street sweeping
- Gravel bag berm



Manuals

➡ Caltrans Storm Water Quality Handbooks

- ⇒ Project Planning and Design Guide
- ⇒ SWPPP / WPCP Preparation Manual
- ⇒ Construction Site BMPs Manual

➡ Revised Construction Manual

➡ New BMP Field Guidance Manual

➡ New Dewatering Guide



Manuals

- ➡ Caltrans Storm Water Quality Handbooks
 - ⇒ Project Planning and Design Guide
 - ⇒ SWPPP / WPCP Preparation Manual
 - ⇒ Construction Site BMPs Manual

- ➡ Revised Construction Manual
- ➡ New BMP Field Guidance Manual (in development)
- ➡ New Dewatering Guide (in development)

Manuals

➡ BMP Field Guidance Manual

- ⇒ “Tool Box” for field personnel
- ⇒ Principles of Erosion and Sediment Control
- ⇒ Trouble Shooting Guide
- ⇒ BMP Selection Installation and Maintenance



Manuals

- ➡ Caltrans Storm Water Quality Handbooks
 - ⇒ Project Planning and Design Guide
 - ⇒ SWPPP / WPCP Preparation Manual
 - ⇒ Construction Site BMPs Manual
- ➡ Revised Construction Manual
- ➡ New BMP Field Guidance Manual (in development)
- ➡ New Dewatering Guide (in development)

Who Wants To Be A Millionaire?



Millionaire Review Question #1

What agency has the authority to enforce the Clean Water Act in California?

A) RWQCB

B) Dept of Fish and Game

C) EPA

D) A, B & C

Millionaire Review Question #2

Construction site erosion can be how many times greater than nature's erosion process?

a) 10 - 100

b) 10 - 1,000

c) Mach 2

d) 100 - 10,000

Millionaire Review Question #3

In the Standard Specifications which section Requires contractors to prepare and implement a program to control water pollution?

a) 16-2.01H

b) 20-1.09P

c) 10-01.10A

d) 7-1.01G

Millionaire Review Question #4

Project Planning and Design Guide, and SWPPP / WPCP Preparation Manual are two of the three new CT Storm Water Quality Handbooks. What is the other one?

a) Construction Manual

b) Construction Site BMP Manual

c) Construction Site ESC Manual

d) ESC Practices Manual

Millionaire Review Question #5

According to the StormWater/CleanWater Protection Program:

One gallon of oil has the potential to contaminate up to how many gallons of water?

a) 100,000

b) 1.5 million

c) 1 million

d) 500,000

Millionaire Review Question #6

Water pollution control requirements are found in this section of the Special Provisions?

a) 16

b) 18

c) 10

d) 5

Video

➡ Hold on to your dirt



Construction Site Best Management Practices

➡ Course Highlights

- ➡ Introduction
- ➡ The Law
- ➡ Recent Fines
- ➡ Permits, Specs and Manuals
- ➡ Construction Site BMPs
- ➡ Inspection Procedures
- ➡ Communication
- ➡ Documentation



Construction Site Best Management Practices

➤ Section Highlights

- ⇒ BMP Installation
- ⇒ Maintenance of BMPs
- ⇒ Missing and Improperly Implemented BMPs

Construction Site Best Management Practices

- **BMP defined – Any program, technology, process, siting criteria, operating method, measure, or device that controls, prevents, removes, or reduces pollution**

BMP Installation

BMP Categories

- ⇒ Temporary Soil Stabilization
- ⇒ Temporary Sediment Control
- ⇒ Wind Erosion Control
- ⇒ Tracking Control
- ⇒ Non-Storm Water Management
- ⇒ Waste Management and Materials Pollution Control


Temporary Soil Stabilization

ID	BMP Name
SS-1	Scheduling
SS-2	Preservation of Existing Vegetation
SS-3	Hydraulic Mulch
SS-4	Hydroseeding
SS-5	Soil Binders
SS-6	Straw Mulch
SS-7	Geotextiles, Plastic Covers, & Erosion Control Blankets/Mats
SS-8	Wood Mulching
SS-9	Earth Dikes/Drainage Swales & Lined Ditches
SS-10	Outlet Protection/Velocity Dissipation Devices
SS-11	Slope Drains

BMP Use - Soil Stabilization SS-1

Scheduling

Example of Graphical Schedule



BMP Installation - Soil Stabilization SS-3 Hydraulic Mulch



Caltrans Requirements

- Mulch must be approved by RE
- Prior to application, roughen embankment and fill areas
- Most types need 24 hours to dry before rainfall occurs
- Application rates per SS3 or manufacturers recommendation

Hydraulically applied paper mulch

BMP Installation - Soil Stabilization SS-4 Hydroseeding



Caltrans Requirements

- Seed mix must comply with the Standard Specifications and Special Provisions
- Hydroseeding mixture requires approval by the Landscape Architect and DSWC
- Prior to application, roughen embankment and fill areas
- Steep slopes are difficult to protect with temporary seeding

Hydroseeded slopes show vegetation growth

BMP Installation - Soil Stabilization

SS-4 Hydroseeding



Unstabilized slope vs. Stabilized slope

BMP Installation - Soil Stabilization SS-5

Soil Binders




Application of Soil Binder

Caltrans Requirements

- Are temporary and may require reapplication
- Soil type will dictate which kind of soil binder to use
- Must be environmentally benign, and shall not stain paved or painted surfaces
- Do not apply during or immediately before a rainfall

BMP Installation - Soil Stabilization SS-6 Straw Mulch



Caltrans Requirements

- Apply straw at a minimum of 2 tons per acre or as per Special Provisions
- A tackifier (glue) is the preferred method of anchoring straw
- Straw needs to last long enough to achieve erosion control objective

BMP Installation - Soil Stabilization



Lack of soil stabilization

BMP Installation - Soil Stabilization SS-7 Geotextiles, Plastic Covers, EC Blankets/Mats



Caltrans Requirements

- Used when disturbed soil may be difficult to stabilize
 - Materials selected by the contractor must be approved by the RE
- Blankets and mats must be removed and disposed of prior to application of permanent soil stabilization

Erosion Control Blankets

BMP Installation – Soil Stabilization SS-9 Earth Dikes/Drainage Swales/Lined Ditches



Caltrans Requirements

- Conveyances shall be stabilized
- Not suitable for trapping sediment
- Do not divert runoff onto other property

BMP Installation – Soil Stabilization SS-9 Earth Dikes/Drainage Swales/Lined Ditches

- ➔ Collect runoff from deck cure



Temporary Sediment Control

ID	BMP Name
SC-1	Silt Fence
SC-2	Desilting Basin
SC-3	Sediment Trap
SC-4	Check Dam
SC-5	Fiber Rolls
SC-6	Gravel Bag Berm
SC-7	Street Sweeping and Vacuuming
SC-8	Sandbag Barrier
SC-9	Straw Bale Barrier
SC-10	Storm Drain Inlet Protection

BMP Installation - Sediment Controls SC-1 Silt Fence




Caltrans Requirements

- Not effective unless keyed in
 - Locate on level contours
- Don't use in streams, channels or anywhere flow is concentrated
 - Locate in areas suitable for ponding and sediment deposition
- Maintain to provide an adequate sediment holding capacity

Incorrect installation of silt fence, bottom portion not properly keyed in, improper overlap



BMP Installation - Sediment Controls SC-1 Silt Fence

Silt Fence




NOTES

1. Construct the length of each reach so that the change in base elevation across the reach does not exceed 0.5% of the base elevation.
2. The last 2.5 m or more shall be turned up slope.
3. Stake dimensions are nominal.
4. Dimensions may vary to fit field conditions.
5. Stakes shall be spaced at 2.5 m maximum and shall be positioned on downstream side of fence.
6. Stakes to anchor and secure fabric to field around each stake and full width, secure fabric to stake with 4 spigots.



JOINING SECTION DETAIL (TOP VIEW)



END STAKE DETAIL (TOP VIEW)

BMP Installation - Sediment Controls SC-1 Silt Fence, SS-6 ~~Straw Mulch~~



Correct installation of silt fence on a slope stabilized with Straw Mulch



Straw Mulch application

BMP Installation - Sediment Controls



BMP Installation - Sediment Controls



Lack of sediment control

BMP Installation - Sediment Controls

SC-3 Sediment Trap



Requirements

- Size limited by availability of right-of-way
- Not appropriate for drainage areas greater than 5ac
- Length of basin must be three times the width
- Safety fencing may be required

Sediment Trap

BMP Installation - Sediment Controls

SC-4 Check Dams




Caltrans Requirements


- Don't use in live streams or channels
- Not to be constructed from straw bales or a silt fence
- High flows shall safely flow over check dam without upstream flooding or damage to check dam
- Backwater from downstream check dam shall reach toe of upstream dam

Check Dams

SC-4



ELEVATION



TYPICAL ROCK CHECK DAM SECTION

ROCK CHECK DAM
NOT TO SCALE



Caltrans Storm Water Quality Handbooks
Construction Site Best Management Practices Manual
November 2000

Check Dams SC-4
3 of 3

BMP Installation - Sediment Controls

SC-5 Fiber Rolls



Caltrans Requirements

- Use along the top, face, and at grade breaks of exposed and erodible slopes
- Locate on level contours
- Do not use in place of a sediment barrier
- Must be trenched in

Incorrect installation of fiber rolls; too far apart,
not trenched in

BMP Installation - Sediment Controls



SC-5 Fiber Rolls



Correct installation of fiber rolls

Fiber Rolls

SC-5



BMP Installation - Sediment Control SC-7 Street Sweeping and Vacuuming



Caltrans Requirements

- Do not use kick brooms or sweeper attachments
- Visible sediment tracking shall be swept and vacuumed daily
- Dispose of sweeper waste at an approved dumpsite

Street sweeping and vacuuming

BMP Installation - Sediment Controls

SC-10 Storm Drain Inlet Protection




Caltrans Requirements


- Use where ponding will not encroach into highway traffic
- For use in areas where grading is complete
- Not for concentrated flows

SC-10

Storm Drain Inlet Protection



SECTION A-A



DI PROTECTION TYPE 1
NOT TO SCALE

NOTES:


1. For use in areas where grading has been completed and final soil stabilization and seeding are pending.
2. Not applicable in paved areas.
3. Not applicable with concentrated flows.

BMP Installation - Sediment Controls


SC-10 Storm Drain Inlet Protection

Storm Drain Inlet Protection

SC-10



Section A-A



DI PROTECTION TYPE 2
NOT TO SCALE

Notes

1. For use in cleared and grubbed and in graded areas.
2. Shape basin so that longest inflow area faces longest length of trap.
3. For concentrated flows, shape basin in 2:1 ratio with length oriented towards direction of flow.



Caltrans Requirements

- Use where ponding will not encroach into highway traffic
- For use in cleared / grubbed and graded areas
- Frequent maintenance is required




BMP Installation - Sediment Controls


SC-10 Storm Drain Inlet Protection

SC-10

Storm Drain Inlet Protection



TYPICAL PROTECTION FOR INLET ON SUMP



TYPICAL PROTECTION FOR INLET ON GRADE

NOTES:

1. Intended for short-term use.
2. Use to inhibit non-storm water flow.
3. Allow for proper maintenance and cleanup.
4. Bags must be removed after adjacent operation is completed.
5. Not applicable in areas with high silts and clays without filter fabric.

Caltrans Requirements

- Use where ponding will not encroach into highway traffic
- Intended for short-term use
- Remove when adjacent operation is complete

Wind Erosion Control

ID

WE-1

BMP Name

Wind Erosion Control



BMP Installation - Wind Erosion Control WE-1



Lack of wind erosion controls

BMP Installation - Wind Erosion Control WE-1



Soil binder applied via water truck

Caltrans Requirements

- Effectiveness depends on soil, temperature, humidity and wind velocity
- Temporary soil stabilizers and soil binders will also provide wind erosion control benefits

Tracking Control

ID	BMP Name
TC-1	Stabilized Construction Entrance/Exit
TC-2	Stabilized Construction Roadway
TC-3	Entrance/Outlet Tire Wash

BMP Installation - Tracking Control TC-1 Stabilized Construction Entrance / Exit



Lack of stabilized entrance / exit


BMP Installation - Tracking Control TC-1 Stabilized Construction Entrance / Exit



Lack of stabilized entrance / exit


BMP Installation - Tracking Control TC-1 Stabilized Construction Entrance / Exit

Stabilized Construction Entrance/Exit **TC-1**



Stabilized Construction Entrance/Exit (Type 1)

TC-1 Stabilized Construction Entrance/Exit



Stabilized Construction Entrance/Exit (Type 2)

BMP Installation - Tracking Control TC-1 Stabilized Construction Entrance / Exit



Caltrans Requirements

- If aggregate is used place over geotextile fabric 12" deep
 - Use 3"-6" diameter rock
 - Minimum of 15 m in length
- Design for heaviest equipment
- Limit number of entrances and exits
 - Require their use

Large diameter rock used as a stabilized entrance / exit.

~~Non-Storm Water Management BMPs~~

ID	BMP Name
NS-1	Water Conservation Practices
NS-2	Dewatering Operations
NS-3	Paving and Grinding Operations
NS-4	Temporary Stream Crossing
NS-5	Clear Water Diversion
NS-6	Illicit Connection / Illegal Discharge Detection and Reporting
NS-7	Potable Water / Irrigation
NS-8	Vehicle and Equipment Cleaning
NS-9	Vehicle and Equipment Fueling
NS-10	Vehicle and Equipment Maintenance

BMP Installation - Non-Storm Water NS-2 Dewatering Operations



Caltrans Requirements

- Notify District Construction Storm Water Coordinator
- Use where groundwater or accumulated precipitation will be discharged from site
- Addresses sediment only
- Notify RE if pollutant other than sediment is present
- Must comply with applicable permits

BMP Installation - Non-Storm Water NS-3 Paving and Grinding Operations



Caltrans Requirements

- Place drip pans under paving equipment when not in use
- Substances used to coat asphalt equipment shall not contain soap, will be non-foaming and non-toxic
- Clean equipment off-site whenever possible

BMP Installation – Non-Storm Water NS-4 Temporary Stream Crossing

Caltrans Requirements

- Use where construction equipment must frequently cross a waterway
- If improperly designed they may increase pollution load through washouts and scouring
- May require RWQCB, USACE, DFG permits / approval



Falsework Construction

BMP Installation – Non-Storm Water NS-4 Temporary Stream Crossing



BMP Installation – Non-Storm Water NS-5 Clear Water Diversion



Caltrans Requirements

- May require RWQCB, USACE, DFG permits / approval
- If improperly designed they may increase pollution load through washouts and scouring
- Construct diversions with material free of potential pollutants

BMP Installation – Non-Storm Water NS-6 Illicit Connection / Illegal Discharge

Caltrans Requirements

- Can be in liquid or solid form
 - Refers to discharges and dumping caused by parties other than contractor
- Inspect site before beginning of job
- Proceed with caution – notify RE at time of discovery



BMP Installation - Non-Storm Water NS-9 Vehicle and Equipment Fueling



Caltrans Requirements

- Fuel on site only when impractical to go off site
- Use a designated area
- Clean up materials and spill kits available
- Protect fueling area from run-on and run-off

Mobile fueling operations require BMPs

BMP Installation - Non-Storm Water NS-9 Vehicle and Equipment Fueling



Pile Driving Operations

Waste Management and Material Pollution Control BMPs

ID	BMP Name
WM-1	Material Delivery and Storage
WM-2	Material Use
WM-3	Stockpile Management
WM-4	Spill Prevention and Control
WM-5	Solid Waste Management
WM-6	Hazardous Waste Management
WM-7	Contaminated Soil Management
WM-8	Concrete Waste Management
WM-9	Sanitary / Septic Waste Management
WM-10	Liquid Waste Management

BMP Installation - Waste Management WM-1 Material Delivery and Storage



**Well maintained
temporary
containment
facility**

**Substances that
require storage in
a containment
facility**



Caltrans Requirements

- Spill containment volume shall be equal to 1.5 times volume of all containers and be impervious to the materials for 72 hours
- Substances listed in 40 CFR Parts 110, 117, and 302 require containment
- Provide cover during non-working days and prior to rain events

BMP Installation - Waste Management WM-1 Material Delivery and Storage



Temporary containment facility for fuel

BMP Installation - Waste Management WM-1 Material Delivery and Storage

- ➡ Cure requires proper storage



BMP Installation - Waste Management WM-3 Stockpile Management



Caltrans Requirements

- Year-round requirement
- Locate away from concentrated flows of storm water
- Protect from run-on

BMP Installation – Waste Management WM-5 Solid Waste Management

Caltrans Requirements

- Solid waste includes litter generated by the public
- Dumpsters of sufficient size and number shall be provided
- Segregate potentially hazardous waste from non-hazardous waste



BMP Installation - Waste Management WM-8 Concrete Waste Management



Concrete washout



Uncontrolled concrete washouts

BMP Installation - Waste Management WM-8 Concrete Waste Management



**Below Grade
concrete washout**



Above Grade concrete washout

Caltrans Requirements

- PCC and AC waste shall not be allowed to enter storm drains and watercourses
- Install signs designating temporary washout areas
- Locate washout facilities a minimum of 15m(50ft) from storm drains, water courses

BMP Installation - Waste Management

WM-9 Sanitary / Septic Waste Management



Locate temporary sanitary facilities
away from drainage facilities

Caltrans Requirements

- Locate sanitary facilities away from storm drains, water courses
- Secure if subject to high wind
- Contractor to monitor weekly

BMP Installation - Waste Management

WM-10 Liquid Waste Management



Caltrans Requirements

- Liquid waste cannot enter storm drain, receiving water or waterway
- Disposal of certain liquid waste may be subject to specific laws or regulations

Tie Back wall construction

Who Wants To Be A Millionaire?



Millionaire Review Question #1

The letters BMP are also known as?

a) Best Materials Practical

b) Big Major Problem

c) Best Method Practice

d) Best Management Practice

Millionaire Review Question #2

Which one of the six BMP categories found in the BMP Manual, includes Scheduling?

a) Soil Stabilization

b) Non-Storm Water Management

c) Sediment Control

d) Tracking Control

Millionaire Review Question #3

Which one of the following is not a Soil Stabilization BMP?

a) Hydraulic Mulch

b) Slope Drains

c) Earth Dikes

d) Desilting Basin

Millionaire Review Question #4

What is the Caltrans minimum required application rate for straw mulch?

a) 2 hectares per acre

b) 2 tons per hectare

c) 20 acres per ton

d) 2 tons per acre

Millionaire Review Question #5

“Keying in the bottom” is an installation requirement of which BMP?

a) Gravel Bag Berms

b) Grocery Bag Berms

c) Silt Fence

d) Geotextiles / Plastic Covers

Millionaire Review Question #6

What is a common way for construction sites to achieve/maintain the rainy season DSA requirement?

a) Apply temporary SC regularly

b) Apply temporary EC regularly

c) Install both silt fence and straw bales

d) Apply permanent SC controls asap

Construction Site Best Management Practices

➡ Course Highlights

- ➡ Introduction
- ➡ The Law
- ➡ Recent Fines
- ➡ Permits, Specs and Manuals
- ➡ Construction Site BMPs
- ➡ Inspection Procedures
- ➡ Communication
- ➡ Documentation



Maintenance of BMPs



Maintenance of BMPs is a critical requirement for an effective water pollution control program

Maintenance of BMPs



Silt fence maintenance

Improperly Implemented BMPs



Silt fence installed incorrectly in a concentrated flow area

Improperly Implemented BMPs



Silt fence installed incorrectly in a unstabilized concentrated flow area

Improperly Implemented BMPs



Sandbags blocking a DI, and causing a safety hazard

Improperly Implemented BMPs



Sandbags blocking a DI, and causing a safety hazard

Improperly Implemented BMPs




Uncontrolled concrete washout near an active DI

Improperly Implemented BMPs

Stabilized entrance / exit on right gets little use vs.
unstabilized area on left



Improperly Implemented BMPs



Possible solution: Block other entrance / exit

Improperly Implemented BMPs



Incorrect use of silt fence

Improperly Implemented BMPs



Lack of soil stabilization has lead to failure of silt fence

Improperly Implemented BMPs



Stockpile should be relocated, covered and protected from run-on